

22-0846

MARITIME PLUMBING AND MECHANICAL LLC

2214 Franklin Street, Manitowoc, WI 54220
(920) 682-8794

Estimate



Name / Address
City of Manitowoc 900 Quay Street Manitowoc WI 54220

Date	Estimate #
9/20/2022	7403B

Project

Description	Qty	Cost	Total
Quote to install water to Llama barn Includes excavating hole near existing meter pit, directionally boring 1" poly line to Llama pen Removing section of concrete and install Woodford frost proof hydrant, backfilled with stone Includes connecting line in existing meter pit with shut off valve Includes heat tape on water line under waterere Includes directionally boring 1" line for electrical at same time Not included Concrete repair Landscaping Removing fencing	1	8,185.00	8,185.00
This estimate is good for 10 days. To proceed, please sign, date and return with 1/2 downpayment.		Total	\$8,185.00

Payments over \$500.00 paid by credit card will be subject to a transaction fee of 3%.



Customer Signature _____