


CITY OF MANITOWOC

WISCONSIN, USA
www.manitowoc.org

21-0378



April 9, 2021

TO: Mayor and Common Council
FROM: Board of Public Works
SUBJECT: 2021 Concrete Paving III (S. 30th St. Reconstruction)
WS-21-8

Dear Mayor and Common Council:

At the April 7, 2021 Board of Public Works meeting, the Board met to receive bids for 2021 Concrete Paving III (S. 30th St. Reconstruction), WS-21-8. City Clerk reported having received one (1) e-bids. Same was opened and accepted online through Quest, and is as follows:

Name	Bid Bond	Base Bid
Vinton Construction Company	Bid Bond	\$1,999,982.67

"Moved by Alderperson James Brey, seconded by Alderperson John Brunner, and unanimously carried to refer the bid to the Director of Public Infrastructure for tabulation and recommendation. Ayes, 8 . Nays, none."

Very Truly Yours,

MACKENZIE REED-KADOW
Secretary Board of Public Works

#WS-21-8 CONCRETE PAVING III (SOUTH 30TH ST RECONSTRUCTION) (#7672169)
 BID DATE: APRIL 7, 2021

Vinton Construction Company

Item #	Item Description	UofM	Qty	Unit Price	Extension
SOUTH 30TH STREET - CONCRETE PAVING				\$1,372,706.42	
1	Mobilization	LS	1	\$40,000.00	\$40,000.00
2	Traffic Control	LS	1	\$16,000.00	\$16,000.00
3	Traffic Control Detour	LS	1	\$6,200.00	\$6,200.00
4	Inlet Protection Type "D"	EA	32	\$95.00	\$3,040.00
5	Furnish, Install & Remove Stone Ditch Bag	EA	33	\$15.00	\$495.00
6	Furnish, Install & Remove Silt Fence	LF	50	\$3.00	\$150.00
7	Tracking Pad	EA	1	\$0.01	\$0.01
8	Temporary Mailboxes (15 boxes per bank)	EA	1	\$1,000.00	\$1,000.00
9	Remove & Replace Mailbox (Complete Unit)	EA	6	\$200.00	\$1,200.00
10	Unclassified Excavation (Incl. Pavement, Curb)	CY	10817	\$17.95	\$194,165.15
11	Stripping Topsoil	SY	7702	\$2.80	\$21,565.60
12	Sawing Concrete or Asphalt Roadway, Full Depth	LF	212	\$3.00	\$636.00
13	Sawing Concrete or Asphalt Driveway, Full Depth	LF	792	\$3.00	\$2,376.00
14	Sawing Concrete Sidewalk, Full Depth	LF	45	\$3.00	\$135.00
15	9" Concrete Pavement w/Integral Curb (Doweled)	SY	13958	\$42.70	\$596,006.60
16	8" Crushed Aggregate Base Course (1-1/4")	SY	15143	\$5.68	\$86,012.24
17	8" Breaker Run Stone Material (6" and down)	SY	15143	\$5.68	\$86,012.24
18	Undistributed Geo-Grid	SY	7000	\$2.25	\$15,750.00
19	Concrete Pavement Gap	EA	9	\$1,000.00	\$9,000.00
20	3/4" Epoxy Coated Tie Bars (Includes Drilling)	EA	83	\$8.00	\$664.00
21	1-1/4" Epoxy Coated Dowel Bars (Includes Drilling)	EA	103	\$13.00	\$1,339.00
22	New 5" Mainline Concrete Sidewalk w/ 2" C.A.B.C. (West Side)	SF	5336	\$5.70	\$30,415.20
23	New 6" Concrete Sidewalk w/ 2" C.A.B.C. (Handicap Ramps & Bus Stops)	SF	435	\$6.50	\$2,827.50
24	Remove & Replace 6" Concrete Sidewalk w/ 2" C.A.B.C.	SF	864	\$7.00	\$6,048.00
25	Remove & Replace 6" Concrete Driveway H.E.S. (7 bag mix) w/ 2" C.A.B.C.	SF	1052	\$7.20	\$7,574.40
26	Remove & Replace 8" Concrete Sidewalk & Driveway H.E.S. (7 bag mix)w/2" C.A.B.C.	SF	7963	\$7.50	\$59,722.50
27	Remove & Replace 8" Concrete Driveway w/Integral Curb H.E.S. (7 bag mix) w/2" C.A.B.C.	SF	6295	\$7.50	\$47,212.50
28	Detectable Warning Fields	SF	80	\$30.00	\$2,400.00
29	Remove and Replace 4" H.M.A., Type 4LT 58-28S w/2" C.A.B.C. (Driveway)	SY	538	\$65.16	\$35,056.08
30	Tack Coat	GAL	28	\$3.89	\$108.92
31	3" Pulverized Topsoil	SY	10607	\$4.89	\$51,868.23
32	Seed (Mixture No. 40), Fertilizer & Water	SY	10607	\$0.75	\$7,955.25
33	Erosion Mat, Urban Class 1, Type A	SY	10607	\$1.10	\$11,667.70
34	Ditching	LF	970	\$5.00	\$4,850.00
35	Corinthian Linden Tree 2" - 2 1/2" B&B	EA	2	\$480.00	\$960.00
36	Street Honey Locust Tree 2" - 2 1/2" B&B	EA	4	\$480.00	\$1,920.00
37	Red Pointe Maple Tree 2" - 2 1/2" B&B	EA	3	\$480.00	\$1,440.00
38	Princeton Elm Tree 2" - 2 1/2" B&B	EA	4	\$480.00	\$1,920.00
39	Yellowwood Tree 2" - 2 1/2" B&B	EA	3	\$480.00	\$1,440.00
40	Frans Fountain Hornbeam Tree 2" - 2 1/2" B&B	EA	2	\$480.00	\$960.00
41	Urban Sunset Maple Tree 2" - 2 1/2" B&B	EA	6	\$480.00	\$2,880.00
42	Sterlins Linden Tree 2" - 2 1/2" B&B	EA	1	\$480.00	\$480.00
43	Prairie Sentinel Hackberry Tree 2" - 2 1/2" B&B	EA	5	\$480.00	\$2,400.00
44	Pavement Marking, Epoxy, 4-Inch	LF	5028	\$1.35	\$6,787.80
45	Pavement Marking, Crosswalk, Epoxy, 6-Inch	LF	102	\$7.50	\$765.00
46	Pavement Marking, Crosswalk, Epoxy, 12-Inch Bars, Alt. (Form #905B)	LF	102	\$12.75	\$1,300.50
SOUTH 30TH STREET - STORM SEWER				\$74,779.15	
47	Utility Line Opening	EA	2	\$480.00	\$960.00
48	Remove Existing Storm Sewer Pipe	LF	24	\$14.85	\$356.40
49	Remove Culvert Pipe	EA	12	\$425.00	\$5,100.00
50	Removing Storm Manholes	EA	1	\$420.00	\$420.00
51	Furnish & Install 6" PVC Underdrain Pipe W/Sock (SDR-35)	LF	10	\$28.00	\$280.00
52	Furnish & Install 12" PVC SDR-35, Storm Sewer	LF	173	\$55.60	\$9,618.80
53	Furnish & Install 15" PVC SDR-35, Storm Sewer	LF	11	\$68.30	\$751.30
54	Furnish & Install 12" CMP Endwall	EA	2	\$200.00	\$400.00
55	Furnish & Install Standard Manhole, Type 1	VF	9.55	\$479.00	\$4,574.45
56	Furnish & Install Standard Manhole, Type 4	VF	25.8	\$479.00	\$12,358.20
57	Furnish & Install Type 3 Catch Basin (2' X 3')	EA	1	\$1,480.00	\$1,480.00
58	Furnish & Install Type 3 Inlet (2' X 3')	EA	3	\$1,480.00	\$4,440.00
59	Furnish & Install Type 1 Field Inlet (2' diameter)	EA	3	\$1,240.00	\$3,720.00
60	Reconstruct Storm Manhole	EA	8	\$1,250.00	\$10,000.00
61	Furnish & Install Type "J" Casting (R-1550-A), Storm	EA	16	\$372.00	\$5,952.00
62	Furnish & Install Type "J" Casting (R-2050-C) Open Grate, Storm	EA	4	\$397.00	\$1,588.00
63	Furnish & Install Type "H" Casting (R-3067-R), Diagonal, Storm	EA	16	\$565.00	\$9,040.00
64	Stone Trench (Form #428A)	LF	42	\$56.00	\$2,352.00
65	Furnish & Install Trench Backfill	TON	80	\$17.35	\$1,388.00
SOUTH 30TH STREET - SANITARY SEWER (NO CDBG FUNDING FOR THIS PORTION)				\$11,047.00	
66	Reconstruct Sanitary Manhole	EA	1	\$1,600.00	\$1,600.00
70	Furnish & Install Type "J" Casting (R-1550-A), with "T" Gasket	EA	13	\$700.00	\$9,100.00
71	Furnish & Install Trench Backfill	TON	20	\$17.35	\$347.00
SOUTH 30TH STREET - WATER MAIN (NO CDBG FUNDING FOR THIS PORTION)				\$429,467.00	
A1	Supply & Install 12-Inch PVC Watermain	LF	2708	\$96.00	\$259,968.00
A2	Supply & Install 8-Inch PVC Watermain	LF	40	\$96.80	\$3,872.00
A3	Supply & Install 12-Inch Gate Valve in Valve Box	EA	5	\$3,200.00	\$16,000.00
A4	Supply & Install 8-Inch Gate Valve in Valve Box	EA	2	\$1,795.00	\$3,590.00
A5	Supply & Install Fire Hydrant w/6-Inch Valve on Hydrant Lead.	EA	5	\$6,927.00	\$34,635.00
A6	Tie into Existing Watermain and Abandon Existing Watermain (main line)	EA	2	\$3,394.00	\$6,788.00
A7	Connect to Existing Watermain (side street)	EA	2	\$2,930.00	\$5,860.00
A8	Furnish & Install Trench Backfill	CY	2700	\$34.70	\$93,690.00
A9	Remove Existing Hydrant	EA	4	\$400.00	\$1,600.00
A10	Abandon Existing Valves	EA	11	\$280.00	\$3,080.00
A11	Supply and Install Insulation (4" Thick)	SF	64	\$6.00	\$384.00
SOUTH 30TH STREET - WATER MAIN (FIXED PRICED ITEMS)				\$43,280.00	
F1	Reconnect 1-1/4" Existing Water Service, SHORT SIDE, w/Anode	EA	2	\$1,004.00	\$2,008.00
F2	Reconnect 1-1/4" Existing Water Service, LONG SIDE, w/Anode	EA	2	\$2,026.00	\$4,052.00
F3	Reconnect 2" Existing Water Service, LONG SIDE, w/Anode	EA	1	\$2,619.00	\$2,619.00
F4	Reconnect 6" Existing Water Service, SHORT SIDE	EA	3	\$2,894.00	\$8,682.00
F5	Reconnect 6" Existing Water Service, LONG SIDE	EA	1	\$3,617.00	\$3,617.00
F6	Reconnect 8" Existing Water Service, LONG SIDE	EA	2	\$4,365.00	\$8,730.00
F7	Reconnect 10" Existing Water Service, SHORT SIDE	EA	2	\$4,301.00	\$8,602.00
F8	Reconnect 12" Existing Water Service, SHORT SIDE	EA	1	\$4,970.00	\$4,970.00
SOUTH 30TH STREET - ADD ALTERNATE #1 (SIDEWALKS ON EAST SIDE)				\$68,703.10	
1A	Alternate New 5" Mainline Concrete Sidewalk w/2" C.A.B.C. (East Side)	SF	11438	\$5.70	\$65,196.60
2A	Alternate New 6" Sidewalk w/2" C.A.B.C. (East Side Handicap Ramps)	SF	281	\$6.50	\$1,826.50
3A	Alternate Detectable Warning Fields	SF	56	\$30.00	\$1,680.00
BASE BID TOTAL:				\$1,999,982.67	

Recommend Awarding to Vinton Construction
 4-13-21