



CITY OF MANITOWOC

WISCONSIN, USA
www.manitowoc.org

May 10, 2022

TO: Mayor and Common Council
FROM: Board of Public Works
SUBJECT: 2022 Concrete Intersection Reconstruction – Cleveland Ave. at Maritime Dr., Project #WS-22-12

Dear Mayor and Common Council:

At the April 20, 2022 Board of Public Works meeting, the Board met to receive bids for 2022 Concrete Intersection Reconstruction – Cleveland Ave. at Maritime Dr., Project #WS-22-12. City Clerk reported having received one (1) e-bid. Same was opened and accepted online through Quest, and is as follows:

Name	Bid Bond	Base Bid
Vinton Construction Co.	Bid Bond	\$89,371.36

"Moved by Finance Director/Treasurer Alfred, seconded by Alderperson Reckelberg and unanimously carried to refer the bid to the Director of Public Infrastructure for tabulation and recommendation. Ayes, 7 . Nays, none."

Very Truly Yours,

MACKENZIE REED-KADOW
Secretary Board of Public Works

#WS-22-12 CONCRETE INTERSECTION RECONSTRUCTION CLEVELAND AVE AT MARITIME DR
 (#8174978)

BID DATE: APRIL 20, 2022

**Vinton Construction
 Company**

Item #	Item Description	UofM	Qty	Unit Price	Extension
Cleveland Avenue & Maritime Drive Intersection					\$89,371.36
1	Mobilization	LS	1	\$17,500.00	\$17,500.00
2	Traffic Control	LS	1	\$8,000.00	\$8,000.00
3	Inlet Protection, Type D (Diaper)	EA	2	\$118.12	\$236.24
4	Unclassified Excavation (Incl. Pavement & Curb)	CY	181	\$38.75	\$7,013.75
5	8" Concrete Pavement W/Integral Curb	SY	315	\$58.72	\$18,496.80
6	6" Crushed Aggregate Base Course	SY	320	\$5.25	\$1,680.00
7	30" Concrete Curb & Gutter (Type A) w/6" Gravel Base	LF	163	\$38.00	\$6,194.00
8	Sawing Existing Concrete Pavement, Full Depth	LF	372	\$3.00	\$1,116.00
9	3/4" Epoxy Coated Tie Bars (Includes Drilling)	EA	149	\$9.00	\$1,341.00
10	Remove Concrete Driveway	SF	230	\$1.00	\$230.00
11	6" Concrete Driveway w/ 2" Gravel Base	SF	596	\$8.50	\$5,066.00
12	Adjust/Rotate Inlet Casting	EA	1	\$600.00	\$600.00
13	Adjust Manhole Casting	EA	2	\$450.00	\$900.00
14	Furnish & Install Type "J" Casting (R-1550-A) Storm	EA	1	\$819.00	\$819.00
15	Relocate Hydrant	LS	1	\$9,680.00	\$9,680.00
16	Borrow (where where old pav't. was removed)	CY	131	\$21.25	\$2,783.75
17	Construct Berm	LS	1	\$500.00	\$500.00
18	3" Pulverized Topsoil	SY	434	\$6.68	\$2,899.12
19	Seed, Fertilizer, and Water	SY	412	\$1.42	\$585.04
20	Erosion Mat, Urban Class 1, Type A w/Jute Netting	SY	434	\$1.49	\$646.66
21	Eradicate 4-Inch Lane Line	LF	30	\$8.00	\$240.00
22	Pavement Marking, 4-Inch, Epoxy	LF	234	\$10.00	\$2,340.00
23	Pavement Marking, Stop Line, 18-Inch, Epoxy	EA	24	\$21.00	\$504.00

BASE BID TOTAL: \$89,371.36

*Recommend
 Vinton
 awarded to
 [Signature]
 5-2-22*