

**Sonja Birr**

---

**From:** Greg Minikel  
**Sent:** Tuesday, June 27, 2017 2:10 PM  
**To:** Matt Smits; Mike Zimmer; Dan Koski  
**Cc:** Steve Herzog; Sonja Birr; Karen Dorow  
**Subject:** FW: Emailing - 20170627121831289.pdf  
**Attachments:** 20170627121831289.pdf

Dan,

This was quite a bit higher than what I had (\$52,000 versus \$30,000). However, I never really thought about how they will need to access the site probably with a ramp to get down there and the overall access is not like being on a flat road. The costs should be higher than normal work on a roadway area, but more than double on many items (18 and 24 inch pipe and the borrow material) seems excessive.

Do we ask RLP (Gravel Pit Contractor) to give us a quote for this work??? That is the only other contract out there that we could have a huge change order added to it.

Another option would be to just bid it with a project next year. This would require us to add this item to the 2018 CAWG list.

Or do we just bite the bullet and move forward?? We do have excess funds in the paving budget since the bids came in so good.

I guess we need to take this to the PI Comm. next Wed. and talk about it with them.

They need to approve it in order to start the process for an unbudgeted request anyway.

---

**From:** Ron Raboine [<mailto:rraboine@vintonwis.com>]  
**Sent:** Tuesday, June 27, 2017 12:23 PM  
**To:** Greg Minikel  
**Subject:** Emailing - 20170627121831289.pdf

Try this

Ron

**This is an EXTERNAL email. STOP. THINK before you CLICK links or OPEN attachments.**

---



# VINTON CONSTRUCTION COMPANY...Road Contractors

An Equal Opportunity Employer  
P.O. Box 1987  
2706 N. Rapids Road  
Manitowoc, Wisconsin 54221-1987  
Office 920-682-0375  
Fax 920-682-2838

6/27/2017

Attn Greg Minikel  
City of Manitowoc

Per your request please find the requested pricing

ITEM	ITEM DESCRIPTION	UOM	QTY	UNIT \$	TOTAL
<b>Viehbahn Street at Lakeside Blvd</b>					
1.	Mobilization	LS	1.00	\$ 4,700.00	\$ 4,700.00
2.	Traffic Control	LS	1.00	\$ 780.00	\$ 780.00
3.	Furnish and Install 24" Class III Concrete Pipe	LF	80.00	\$ 133.00	\$ 10,640.00
4.	Furnish and Install 18" HDPE Pipe ( Storm Sewer)	LF	55.00	\$ 126.00	\$ 6,930.00
5.	Furnish and Install 24" Concrete Apron Endwall	EA	1.00	\$ 1,096.00	\$ 1,096.00
6.	Furnish and Install Standard Manhole, Storm	VF	18.35	\$ 314.00	\$ 5,761.90
7.	Furnish and Install Type J Manhole Casting (R-1550-A) Storm	EA	1.00	\$ 314.00	\$ 314.00
8.	Furnish and Install 3" Pulverized Topsoil	SY	903.00	\$ 6.70	\$ 6,050.10
9.	Furnish and Install Seed, Fertilizer, E-mat and Watering	SY	903.00	\$ 5.50	\$ 4,966.50
10.	Furnish and Install 12-18" Rip Rap with Filter Fabric	Ton	40.00	\$ 67.50	\$ 2,700.00
11.	Clearing and Grubbing	ID	26.00	\$ 29.80	\$ 774.80
12.	Furnish and Install Borrow/Fill material	CY	600.00	\$ 12.85	\$ 7,710.00
<b>TOTAL FOR PROJECT</b>				<b>\$52,423.30</b>	

Per discussion:

There were no erosion control items included in the request for pricing, looking at the site we thought there should at minimum be the following:

Tracking Pad (Placement and Removal)	1	ea	\$	2,000.00
Inlet Protections	2	ea	\$	50.00

Not sure if silt fence or rock bags should also be included, so none are included at this point.

Vinton Construction  
Ron Raboine