

SC Concrete

4210 Delta ST
 Manitowoc WI 54220
 (920) 323-4583
 tj@sciler.us

19-0355

Estimate

Date	Estimate #
3/26/2019	2366

Name / Address
City of Manitowoc 900 Quay ST Manitowoc, WI 54220

Description	Qty	Total
Estimate for Walkway and Slab at Washington Park		
15'x6', Walkway, and 30'x50' slab 5" thick , reinforced with 1/2" Rebar 1590 total sqft		
We will: Excavate concrete, asphalt, grass area as needed and haul away		
: Supply and place 4" of gravel fill and compact		
: Form, Setup, Pour and Finish concrete		
: Lastly saw cut, Place topsoil around new concrete and seed		
Cubic yards of concrete	26	3,146.00
Cubic yards of Gravel fill about 4" under concrete	20	400.00
1/2" Rebar	89	645.25
Concrete cure and sealer	5	125.00
Labor in total man hours	105	5,460.00

If Estimate is accepted please sign and return one copy: X _____	Total	\$9,776.25
---	--------------	-------------------

Terms:
50% Down On Site preparation
Balance Due Upon Completion