

Capital Project Request Form



Request Type:

Department: Date:

Title of Request:

Department Priority

Linked to another project?
☐ Yes
☒ No

Project Request is: ☐ New
☒ Replacement
☐ Modification

Estimated Useful Life:

This is a limited field, please attach documents for more detail.

Description:

Basis of Cost: ☐ Quote
☒ Bid
☐ Estimate

Total Cost

Revenue (if any) Net Cost

Will there be additional costs in future years to complete this project?

select one: ☐ Yes
☒ No

If yes, amount?


Finance Dept: Account

Sent to Dept: ☐

Action:

Approve up to \$58,237

to repair/replace Sidewalk
Near Stetson & Madison Museum

A+E	NA-
	
	
NUR	
TMB	
	

#WS-18-17 SIDEWALK REPLACEMENT AT MARITIME MUSEUM (#5919366)
 BID DATE: SEPTEMBER 5, 2018

Seiler Bros.
 Construction Inc

Item #	Item Description	UoM	Qty	Unit Price	Extension
--------	------------------	-----	-----	------------	-----------

PART "A" STATION 0+00 TO 1+67					
1	6" CONCRETE SIDEWALK (REMOVE & REPLACE)	SF	1600	\$8.10	\$12,960.00
2	FURNISH & INSTALL 1-1/4" C.A.B.C.	TON	112	\$45.95	\$5,146.40
3	FURNISH & INSTALL GEOTEXTILE FABRIC, TYPE SAS, NON-WOVEN	SY	167	\$5.70	\$951.90
4	FURNISH & INSTALL STEEL ANGLE (4" X 4" X 3/8")	LF	167	\$13.60	\$2,271.20
5	RELAY STORM SEWER, 18" PVC PIPE (C-900)	LF	14	\$165.00	\$2,310.00
6	3/8" TIE BARS (INC. DRILLING)	EA	10	\$22.00	\$220.00
7	SAWING SIDEWALK (FULL DEPTH)	LF	30	\$9.40	\$282.00
PART "B" STATION 1+67 TO 4+52					
8	6" CONCRETE SIDEWALK (REMOVE & REPLACE)	SF	2800	\$8.10	\$22,680.00
9	FURNISH & INSTALL 1-1/4" C.A.B.C.	TON	50	\$45.95	\$2,297.50
10	FURNISH & INSTALL GEOTEXTILE FABRIC, TYPE SAS, NON-WOVEN	SY	127	\$5.70	\$723.90
11	FURNISH & INSTALL STEEL ANGLE (4" X 4" X 3/8")	LF	285	\$13.60	\$3,876.00
12	3/8" TIE BARS (INC. DRILLING)	EA	90	\$22.00	\$1,980.00
13	SAWING SIDEWALK (FULL DEPTH)	LF	270	\$9.40	\$2,538.00

BASE BID TOTAL:				\$58,236.90
-----------------	--	--	--	-------------