



CITY OF MANITOWOC

WISCONSIN, USA

www.manitowoc.org

March 5, 2026

TO: Mayor and Common Council
FROM: Board of Public Works
SUBJECT: 2026 Concrete Paving I Program – Project #WS-26-1

Dear Mayor and Common Council:

At the March 4, 2026, Board of Public Works meeting, the Board met to receive bids for 2026 Concrete Paving I Program - Project #WS-26-1. City Clerk reported having received one (1) e-bid. Same was opened and accepted online through Quest, and is as follows:

Name	Bid Bond	Base Bid
Vinton Construction Company	Bid Bond	\$1,911,997.76

“Moved by Nycz, seconded by Beeman, and unanimously carried to refer the bid to the Department of Public Infrastructure for tabulation and recommendation. Ayes, 6. Nays, none.”

Very Truly Yours,

MACKENZIE REED

Secretary Board of Public Works

#WS-26-1 2026 CONCRETE PAVING I PROGRAM (#10067211)
 BID DATE: 03/04/2026 04:00 PM CST

Vinton Construction Company

Item #	Item Description	UofM	Quantity	Unit Price	Extension
VIEBAHN STREET (SOUTH 10TH ST TO LAKESIDE BLVD) - CONCRETE PAVING				\$796,709.80	
1	Mobilization	LS	1	\$68,000.00	\$68,000.00
2	Traffic Control	LS	1	\$15,000.00	\$15,000.00
3	Inlet Protection Type "D" (Diaper)	EA	16	\$125.00	\$2,000.00
4	Sediment Log	LF	36	\$8.00	\$288.00
5	Grubbing	ID	51	\$30.00	\$1,530.00
6	Temporary Mailboxes (15 boxes per bank)	EA	1	\$300.00	\$300.00
7	Remove & Replace Mailbox (Complete Unit)	EA	12	\$100.00	\$1,200.00
8	Unclassified Excavation (Incl. Pavement and Curb)	CY	4862	\$23.45	\$114,013.90
9	8" Concrete Pavement w/ Integral Curb (Doweled)	SY	6718	\$62.76	\$421,621.68
10	4" Crushed Aggregate Base Course (1 1/4")	SY	7320	\$3.70	\$27,084.00
11	12" Breaker Run Stone Material (6" and down)	SY	7293	\$10.70	\$78,035.10
12	Undistributed Geo-Grid	SY	3646	\$1.00	\$3,646.00
13	Sawing Concrete or Asphalt Pavement, Full Depth	LF	229	\$3.50	\$801.50
14	Sawing Concrete Driveway/Sidewalk, Full Depth	LF	305	\$3.50	\$1,067.50
15	3/4" Epoxy Coated Tie Bars (Includes Drilling)	EA	67	\$10.00	\$670.00
16	1 1/4" Epoxy Coated Tie Bars (Includes Drilling)	EA	28	\$16.50	\$462.00
17	Remove and Replace 4" Concrete Sidewalk w/ 2" C.A.B.C.	SF	1142	\$10.50	\$11,991.00
18	Remove and Replace 6" Concrete Sidewalk w/ 2" C.A.B.C.	SF	2429	\$11.50	\$27,933.50
19	Detectable Warning Fields (Natural Patina)	SF	56	\$35.00	\$1,960.00
20	30" Concrete Curb & Gutter, Type "D", 6" Thick (Removed and Replaced) w/2" C.A.B.C.	LF	20	\$85.00	\$1,700.00
21	Remove and Replace 3" H.M.A., Type 4LT 58-28S	SY	27	\$217.25	\$5,865.75
22	3" Pulverized Topsoil	SY	1301	\$4.90	\$6,374.90
23	Seed (Mixture No. 40), Fertilizer & Water	SY	1301	\$1.39	\$1,808.39
24	Erosion Mat, Urban Class 1, Type A,(w/ Jute Webbing Material)	SY	1301	\$2.58	\$3,356.58
VIEBAHN STREET (SOUTH 10TH ST TO LAKESIDE BLVD) - STORM SEWER				\$189,511.69	
25	Removing Existing Storm Sewer Pipe	LF	243	\$17.28	\$4,199.04
26	Removing Existing Storm Inlet	EA	3	\$467.00	\$1,401.00
27	Removing Existing Storm Structure	EA	2	\$2,488.00	\$4,976.00
28	Furnish & Install 6" PVC Underdrain Pipe W/Sock (SDR-35)	LF	10	\$52.00	\$520.00
29	Furnish & Install 6" PVC (SDR-35)	LF	28	\$52.00	\$1,456.00
30	Reconnect Building Storm Sewer	EA	2	\$797.00	\$1,594.00
31	Furnish & Install 6" Storm Cleanout	EA	2	\$458.00	\$916.00
32	Furnish & Install 12" PVC (SDR-35), Storm Sewer	LF	271	\$119.70	\$32,438.70
33	Furnish & Install 15" RCP Class III, Storm Sewer	LF	548	\$122.60	\$67,184.80
34	Relay 15" RCP Class III, Storm Sewer	LF	10	\$125.10	\$1,251.00
35	Furnish & Install 18" RCP Class III, Storm Sewer	LF	62	\$108.20	\$6,708.40
36	Relay 18" RCP Class III, Storm Sewer	LF	55	\$110.30	\$6,066.50
37	Furnish & Install Type 3 Catch Basin (2' X 3')	EA	8	\$3,060.00	\$24,480.00
38	Furnish & Install Standard Manhole, Type 4, Storm	VF	10.45	\$845.00	\$8,830.25
39	Furnish & Install Type "J" Casting (R-1550-A), Storm	EA	3	\$1,098.00	\$3,294.00
40	Furnish & Install Type "H" Casting (R-3067-R Diagonal), Storm	EA	11	\$1,382.00	\$15,202.00
41	Furnish & Install Trench Backfill	TON	1371	\$4.00	\$5,484.00
42	Televise Storm sewer	LF	675	\$5.20	\$3,510.00
VIEBAHN STREET (SOUTH 10TH ST TO LAKESIDE BLVD) - SANITARY SEWER				\$142,989.24	
43	Reconnect Sanitary Building Service	EA	15	\$3,800.00	\$57,000.00
44	Furnish and Relay 6" PVC (SDR-35) Building Service	LF	352	\$162.97	\$57,365.44
45	Furnish and Relay 8" PVC (SDR-35) Sanitary Sewer	LF	79	\$105.40	\$8,326.60
46	Furnish & Install Type "J" Casting (R-1550-A), with "T" Gasket	EA	5	\$1,120.00	\$5,600.00
47	Furnish & Install Trench Backfill	TON	1125	\$4.00	\$4,500.00
48	Televise Existing Sanitary Sewer	LF	1961	\$5.20	\$10,197.20
VIEBAHN STREET (SOUTH 10TH ST TO LAKESIDE BLVD) - WATER SERVICE				\$4,120.00	
49	Adjust Water Service	EA	10	\$260.00	\$2,600.00
50	Adjusting 5" Valve Box Cover	EA	4	\$380.00	\$1,520.00

*Recommend Awarding
 to Vinton Construction Co.
 [Signature] 3-9-26*

LANCER CIRCLE - CONCRETE PAVING				\$611,045.73	
51	Mobilization	LS	1	\$35,000.00	\$35,000.00
52	Traffic Control	LS	1	\$13,000.00	\$13,000.00
53	Inlet Protection Type "D" (Diaper)	EA	15	\$125.00	\$1,875.00
54	Temporary Mailboxes (15 boxes per bank)	EA	1	\$300.00	\$300.00
55	Remove & Replace Mailbox (Complete Unit)	EA	4	\$100.00	\$400.00
56	Unclassified Excavation (Incl. Pavement)	CY	3382	\$22.71	\$76,805.22
57	8" Concrete Pavement(Doweled)	SY	5074	\$62.76	\$318,444.24
58	4" Crushed Aggregate Base Course (1 1/4")	SY	5074	\$3.50	\$17,759.00
59	12" Breaker Run Stone Material (6" and down)	SY	5074	\$9.70	\$49,217.80
60	Undistributed Geo-Grid	SY	3806	\$1.00	\$3,806.00
61	Concrete Pavement Gap	EA	1	\$1,500.00	\$1,500.00
62	Driveway Pavement Gap	EA	1	\$500.00	\$500.00
63	Sawing Concrete Pavement, Full Depth	LF	2215	\$3.00	\$6,645.00
64	Sawing Concrete Driveway/Sidewalk, Full Depth	LF	90	\$3.50	\$315.00
65	3/4" Epoxy Coated Tie Bars (Includes Drilling)	EA	893	\$10.00	\$8,930.00
66	Remove and Replace 4" Concrete Sidewalk w/ 2" C.A.B.C.	SF	587	\$10.00	\$5,870.00
67	Remove and Replace 6" Concrete Sidewalk w/ 2" C.A.B.C.	SF	2404	\$10.90	\$26,203.60
68	Detectable Warning Fields (Natural Patina)	SF	56	\$35.00	\$1,960.00
69	30" Concrete Curb & Gutter, Type "A", 8" Thick	LF	613	\$65.00	\$39,845.00
70	3" Pulverized Topsoil	SY	301	\$4.90	\$1,474.90
71	Seed (Mixture No. 40), Fertilizer & Water	SY	301	\$1.39	\$418.39
72	Erosion Mat, Urban Class 1, Type A,(w/ Jute Webbing Material)	SY	301	\$2.58	\$776.58
LANCER CIRCLE - STORM SEWER				\$159,991.30	
73	Removing Existing Storm Sewer Pipe	LF	269	\$14.00	\$3,766.00
74	Removing Storm Inlet	EA	11	\$467.00	\$5,137.00
75	Removing Storm Manhole	EA	6	\$700.00	\$4,200.00
76	Furnish & Install 4" PVC (SDR-35), Storm Sewer	LF	11	\$49.65	\$546.15
77	Reconnect Building Storm Sewer	EA	1	\$797.00	\$797.00
78	Furnish & Install 6" PVC Underdrain Pipe W/Sock (SDR-35)	LF	10	\$52.00	\$520.00
79	Furnish & Install 12" RCP Class IV, Storm Sewer	LF	268	\$99.70	\$26,719.60
80	Furnish & Relay 12" RCP Class IV, Storm Sewer	LF	32	\$101.30	\$3,241.60
81	Furnish & Install 15" RCP Class III, Storm Sewer	LF	27	\$109.65	\$2,960.55
82	Furnish & Install Type 3 Catch Basin (2' X 3')	EA	10	\$3,250.00	\$32,500.00
83	Furnish & Install Standard Manhole, Type 1, Storm	VF	13.39	\$1,200.00	\$16,068.00
84	Furnish & Install Non-Standard Manhole, Type 7, Storm	VF	4.32	\$3,500.00	\$15,120.00
85	Furnish & Install Non-Standard Catch Basin Manhole, Type 9, Storm	VF	10.66	\$1,640.00	\$17,482.40
86	Furnish & Install Type "J" Casting (R-1550-A), Storm	EA	4	\$1,098.00	\$4,392.00
87	Furnish & Install Type "H" Casting (R-3067-R Diagonal), Storm	EA	11	\$1,382.00	\$15,202.00
88	Furnish & Install Type "H" Casting (R-3290-R), Storm	EA	1	\$1,448.00	\$1,448.00
89	Furnish & Install Trench Backfill	TON	471	\$21.00	\$9,891.00
LANCER CIRCLE - SANITARY SEWER				\$4,480.00	
90	Furnish & Install Type "J" Casting (R-1550-A), with "T" Gasket	EA	4	\$1,120.00	\$4,480.00
LANCER CIRCLE - WATER SERVICE				\$3,150.00	
91	Remove Water Manhole	EA	2	\$1,195.00	\$2,390.00
92	Adjusting 5" Valve Box Cover	EA	2	\$380.00	\$760.00
BASE BID TOTAL:				\$1,911,997.76	