



PROPOSAL #107928

Date: September 10, 2024

Submitted to:

Backus Electric
Attention: Brad Walske
920-242-7579
Brad.Walske@BackusElectric.com

Project:

Manitowoc Zoo
Service Outlet Bores

We hereby submit specifications and estimates for the following work and material as listed.

Elexco to:

- Elexco will have all public (registered) utilities located prior to start of work. Owner shall have any private (unregistered) underground lines on site marked. Elexco will not be responsible for any unmarked lines. Backus to locate all private power on premises, and assist with any locates required by the city.
- Supply and install approximately 1,600 feet of 1" schedule 40 electrical rated HDPE via directional bore. Eight separate shots included.
- Stub up 1-inch in (16) locations and leave 1" Shur-Lok connector to convert to PVC. Leave all pits open for Backus to convert and install posts for outlets.
- Remove approximately 20 sq ft of asphalt at Field House. Asphalt replacement not included.
- No restoration included.
- No cobble or solid rock boring included. If encountered, cobble to billed at \$28/ft additional, and solid rock at \$65/ft.

TOTAL: \$16,650.00

O: 920.833.2736 F: 920.833.7468 www.ELEXCOINC.com

423 E. BRONSON ROAD SEYMOUR, WI 54165

Initials _____